

Faulkey Gully MUD System

The water, wastewater and storm drainage facilities in the District have been designed in accordance with accepted engineering practices and the rules and regulations of certain governmental agencies having regulatory or supervisory jurisdiction over the construction and operation of such facilities. Those agencies include, among others, the Texas Commission on Environmental Quality (TCEQ), the City of Houston (COH or “City”), the Engineering Department of Harris County Flood Control District, and Harris County Engineering Department.

The District has two water plants that receive groundwater from three water wells. Water Plant #1 is supplied from the District’s water well #1 and remote water well #3, and Water Plant #2 is supplied from water well #2.

The District operates the Faulkey Gully Sewage Treatment Plant (STP). The wastewater collection and treatment system consists of a jointly-owned sewage treatment plant with a rated capacity of 1,420,000 gallons per day (gpd), with 86.97% owned by the District and 13.03% owned by Malcomson Road Utility District. The sewage treatment collection system includes an on-site lift station and four off-site lift stations.

The District has emergency generators for use at its water and wastewater treatment facilities. The District has also established agreements with three other municipal utility districts to provide additional water to its customers in the event of an emergency.

The operations of the District’s waterworks and wastewater facilities are subject to regulation by, among others, the United States Environmental Protection Agency (EPA), the TCEQ, Harris County Public Health and Environmental Services (the “Health Department”), and the City of Houston.

2017 Security Contract

The District has entered into a security contract with Harris County for one deputy on a 70% basis, with security service provided by Harris County Constable Precinct #4. The contract is effective from 3/1/2017 to 3/1/2018.